DomeSim Investor Pitch

you-take by Codex

We are building a modest, livable starting place for veterans, single mothers, craftsmen, college students, and bachelors. The product is basic infrastructure people can own, maintain, and improve as their lives change. A home should leave its owner enough money and time to build a life around it.

Think of it as a "glorified storage building" developed for living: a simple enclosure with the structure, weather protection, insulation, ventilation, utilities, and usable interior that occupancy requires. Keep the starting specification focused on everyday usefulness. Put effort into dependable essentials and connections that allow future improvements.

The audiences share a need for an attainable starting point, but their interiors will differ. A veteran may want independence and a practical community. A single mother needs predictable costs, privacy, and appropriate sleeping space for her family. A craftsman needs useful workspace. A student needs a stable base while studying; a bachelor may want a modest home that can adapt when his life changes. A common building platform should accommodate those differences.

The ownership template is the RV-and-pad arrangement. The occupant owns the building; a host provides prepared ground and service connections. The objective is to keep compatible equipment and improvements through repairs, upgrades, or relocation between qualified sites. Hosts invest in reusable site infrastructure, while owners invest in their own space. The RV comparison explains ownership and connections; the residential configuration still needs its own approval. Relocation is a planned operation, not effortless travel.

The benefits stack. A stripped-down construct reduces the variety of parts and decisions. Standard parts let a shop repeat fixtures, tasks, and checks. Repetition concentrates training and improvement on a manageable workflow, so each measured reduction in waste or rework can benefit later units. Modular panels and an accessible utility core are designed to support repair and upgrades. A defined pad interface separates site infrastructure from reusable building components. Together, these choices can simplify supply, preserve useful components, and make expansion less disruptive.

This is the code-house principle: shared specifications, reusable components, clear interfaces, testing, and continual improvement applied to a building. The existing software connects geometry to drawings, quantities, estimates, and instructions. The universal element is a defined family of compatible interfaces. The scale opportunity comes from qualifying that family, then repeating it: local fabricators could reproduce the plans, other makers could supply compatible components, and hosts could add serviced pads. Each participant expands the usefulness of the same system.

The case for resilience is that the platform has several useful applications to test. Storage buildings, workshops, studios, and residential packages can reuse a common production core while serving different customers. They can be validated in stages, with tooling and knowledge carried forward. Demand, margins, and suitability must be proved for each use. Large scale becomes plausible when the next building repeats a validated process and the next use configures the same platform.

The investment should establish a qualified residential prototype, measured fabrication and delivered costs, durable enclosure performance, workable host arrangements, and repeatable production. Then expand from demonstrated results. The aim is an enterprise that makes dependable starting space widely available, gives owners a way to improve without starting over, and earns its growth by making the same useful system better.

DomeSim Investor Numbers

USD model estimates recomputed October 14 2026

Reference is the **base infrastructure article**: customer-supplied trees, soft cap, utility core, window AC and **zero quilt insulation**. Solver geometry: 19.42 ft across; 277 sq ft of ten-sided floor; 40 panels of two shapes and 120 members. This is not a finished residential-home price.

Model input	Declared assumption	Model input	Declared assumption
Loaded labor rate	$28/hour	Shop overhead	18.0% of direct cost
Warranty reserve	4.0% of direct cost	Maker markup	20.0% of build cost
Regional freight	$1,250	Timber acquisition	$0; owner supplies trees

Unit economics	USD
Materials and components	$6,337.23
Shop/yard labor (67.3 hours)	$1,884.26
Direct cost subtotal	$8,221.49
Overhead allowance	$1,479.87
Warranty reserve	$328.86
Modeled build cost	$10,030.22
Base article list price	$12,036.26
Price less build cost	$2,006.04
Share of selling price	16.7%

Margin math: $10,030.22 x (1 + 20.0%) = $12,036.26. ($12,036.26 - $10,030.22) / $12,036.26 = 16.7%. This is surplus after modeled overhead and warranty, not after-tax profit or investor return.

Campaign allocation	USD
Production tooling	$60,800
Validation and R&D	$34,850
Quilts and fulfillment	$14,350
Declared total	$110,000

Budget reconciliation: the test dome/pad line is $4,200; the modeled base build plus pad is $16,270. If that line must fund this scope, its gap is $12,070. Replacing only it gives $122,070 before fees and contingency. Salary and marketing are not itemized in the declared goal.

Placement scope: buyer dome plus freight $13,286; separate host pad $6,240; combined base infrastructure $19,526. Land, tax, complete site development, residential fit-out/insulation, and customer-site setup remain outside this package.

Build-cost scenario	Modeled cost	Price less cost	Share of price
Baseline	$10,030.22	$2,006.04	16.7%
Cost +10%	$11,033.24	$1,003.02	8.3%
Cost +20%	$12,036.26	$0.00	0.0%

Repeatability target: 20% fewer modeled labor hours would save 13.5 hours and $460/unit including proportional overhead/warranty, at unchanged rates. This is a scenario, not an achieved improvement. Sale price is held fixed in the sensitivity table.

Before underwriting scale: measure person-hours, site setup, finished occupancy costs, production capacity, demand and working capital. The 67.3-hour estimate is shop/yard work, not a complete-home schedule. Model validators passed; physical performance and operating break-even still need evidence.

Calculation sources: seed_model.quote(), seed_model.seed_geometry(), kickstarter.cost_stack() and kickstarter.goal_lines(). Material rates and the campaign budget are project allowances, not new supplier quotations.